

Floor	Room/area	Labor: Installation description			Material description		Material cost		Labor cost		Combined Line total=	
		Qty.	Item	Installation description:	Qty.	Manufacturer	Assembly	Each	Total	Each		Total
Main	Kitchen	2	GFI outlet	GFI receptacle	2	Leviton	GFI receptacle assembly	\$24.00	\$48.00	\$75.00	\$150.00	\$198.00
		2	Outlet	20 amp 120 volt duplex receptacle	2	Leviton	20a receptacle box assembly/remodel/standard/plastic	\$12.00	\$24.00	\$75.00	\$150.00	\$174.00
		1	4plex outlet	20 amp 120 volt 4plex receptacle	1	Leviton	20a receptacle box assembly/standard/plastic/4plex	\$15.00	\$15.00	\$80.00	\$80.00	\$95.00
		2	Island outlet	20 amp 120 volt duplex receptacle	2	Leviton	20a receptacle box assembly/remodel/standard/plastic	\$15.00	\$30.00	\$110.00	\$220.00	\$250.00
		1	Fridge	20 amp 120 volt duplex receptacle	1	Leviton	20a receptacle box assembly/standard/plastic	\$12.00	\$12.00	\$75.00	\$75.00	\$87.00
		1	Hood vent	Direct wire 120 volt wiring	1	Misc.	Wiring assembly; wire, connectors, straps, hardware	\$8.00	\$8.00	\$75.00	\$75.00	\$83.00
		1	Disposal	20 amp 120 volt duplex receptacle	1	Leviton	20a receptacle box assembly/standard/plastic+pigtail	\$16.00	\$16.00	\$100.00	\$100.00	\$116.00
		1	Disposal switch	To activate disposal motor.	1	Leviton	1pole toggle switch box assembly/standard wh	\$10.00	\$10.00	\$75.00	\$75.00	\$85.00
		1	Dishwasher	20 amp 120 volt duplex receptacle	1	Leviton	20a receptacle box assembly/standard/plastic+pigtail	\$16.00	\$16.00	\$125.00	\$125.00	\$141.00
		1	Range	50 amp 240 volt receptacle	1	Leviton	50 amp 240 volt receptacle assembly & pigtail	\$40.00	\$40.00	\$100.00	\$100.00	\$140.00
		1	U.C. Lite system	Install owner supplied undercabinet light system with remote transformer.	1	Misc.	Wiring assembly; wire, connectors, straps, hardware	\$40.00	\$40.00	\$280.00	\$280.00	\$320.00
		1	1pole switch	To control undercabinet light system.	1	Leviton	1pole toggle switch box assembly/standard wh	\$10.00	\$10.00	\$75.00	\$75.00	\$85.00
		2	New circuit	Circuit homerun= (2)20 amp 120 volt	2	Misc.	Circuit assembly= (1)12-3 romex cable.	\$65.00	\$130.00	\$100.00	\$200.00	\$330.00
		1	New circuit	Circuit homerun= (2)15 amp 120 volt	1	Misc.	Circuit assembly= (1)14-3 romex cable.	\$55.00	\$55.00	\$100.00	\$100.00	\$155.00
		1	New circuit	Circuit homerun= (1)50 amp 240 volt	1	Misc.	Circuit assembly= (1)6-3 romex cable.	\$175.00	\$175.00	\$210.00	\$210.00	\$385.00
								\$0.00		\$0.00	\$0.00	\$0.00
Main	Hall	1	New outlet	15 amp 120 volt duplex receptacle	1	Leviton	15a receptacle box assembly/standard/plastic	\$12.00	\$12.00	\$100.00	\$100.00	\$112.00
								\$0.00		\$0.00	\$0.00	\$0.00
								\$0.00		\$0.00	\$0.00	\$0.00
Main	Full bath	1	GFI outlet	GFI receptacle	1	Leviton	GFI receptacle assembly	\$24.00	\$24.00	\$110.00	\$110.00	\$134.00
		1	Future fan	Install wire in ceiling for future exhaust fan, cap off in junction box for now.	1	Misc.	Wiring assembly; wire, connectors, straps, hardware	\$8.00	\$8.00	\$75.00	\$75.00	\$83.00
		1	1pole switch	Install switch location for future fan.	1	Leviton	1pole toggle switch box assembly/standard wh	\$10.00	\$10.00	\$110.00	\$110.00	\$120.00
		1	New circuit	Circuit homerun= (1)20 amp 120 volt	1	Misc.	Circuit assembly= (1)12-2 romex cable.	\$36.00	\$36.00	\$100.00	\$100.00	\$136.00
								\$0.00		\$0.00	\$0.00	\$0.00
								\$0.00		\$0.00	\$0.00	\$0.00
Main	Half bath	1	GFI outlet	GFI receptacle	1	Leviton	GFI receptacle assembly	\$24.00	\$24.00	\$110.00	\$110.00	\$134.00
		1	New circuit	Circuit homerun= (1)20 amp 120 volt	1	Misc.	Circuit assembly= (1)12-2 romex cable.	\$25.00	\$25.00	\$75.00	\$75.00	\$100.00
								\$0.00		\$0.00	\$0.00	\$0.00
								\$0.00		\$0.00	\$0.00	\$0.00
Main	Office	1	New outlet	20 amp 120 volt duplex receptacle	1	Leviton	20a receptacle & circuit assembly	\$25.00	\$25.00	\$75.00	\$75.00	\$100.00
								\$0.00		\$0.00	\$0.00	\$0.00
								\$0.00		\$0.00	\$0.00	\$0.00
Main	Exterior	1	Service	Replace existing mast and meter, refeed existing breaker panel, connect panel to existing ground rod system, run/install main water bonding wire + bond hot/cold. New equipment to be 200 amps. Install additional auxillary ground bar in existing panel.	1	Misc.	Mast & meter assembly, grounding materials, service conductors, hardware. Provide ground bar for panel.	\$390.00	\$390.00	\$920.00	\$920.00	\$1,310.00
								\$0.00		\$0.00	\$0.00	\$0.00
								\$0.00		\$0.00	\$0.00	\$0.00
								\$0.00		\$0.00	\$0.00	\$0.00
								\$0.00		\$0.00	\$0.00	\$0.00
								\$0.00		\$0.00	\$0.00	\$0.00
Main	All	1	Allowance	Demo, reroute, and/or delete existing wiring as needed. Maintain power if needed.	1	Allowance	Allowance for misc materials.	\$25.00	\$25.00	\$280.00	\$280.00	\$305.00
								\$0.00		\$0.00	\$0.00	\$0.00
All areas of work		1	Permit	Charge for processing fee.	1	State L&I	Permit for all work included. Price is subject to change.	\$125.00	\$125.00	\$65.00	\$65.00	\$190.00
								Parts total=		Labor total=		Grand total=
								\$1,333.00		\$4,035.00		\$5,368.00

BID# FM-504 Date of last revision: N/A